

Gate Burton Energy Park

Preliminary Environmental Information Report

Volume 3, Appendix 11-D: Noise Modelling

June 2022

Gate Burton Energy Park Limited

Quality information

Prepared by

ER

Checked by

YL

Verified by

YL

Approved by

YL

Prepared for:

Gate Burton Energy Park Limited

Prepared by:

AECOM Limited

© 2022 AECOM Limited. All Rights Reserved.

This document has been prepared by AECOM Limited ("AECOM") for sole use of our client (the "Client") in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.



Table of Contents

1.	Noise Modelling	1
1.2	Construction Noise.....	1
1.3	Operational Noise	2

1. Noise Modelling

1.1.1 In order to determine potential operational noise emissions from the development, noise prediction models have been prepared using the CadnaA® v2022 software package. The following assumptions were applied in noise models:

- The ground acoustic absorption has been set to 0.8 (i.e. assumed soft ground conditions which is considered appropriate for predominantly open grass field and farmland);
- The maximum order of reflections was 1;
- Air temperature was assumed to be 10 degrees and humidity 70%;
- Building massing in the surrounding area outside of the DCO Site boundary has been sourced from Ordnance Survey Open Map data and modelled with a standard height of 7m.
- Land topography has been sourced from Ordnance Survey Open Map data; and
- No boundary fences/walls have been included in the noise model; and
- Receiver points have been modelled as 1.5m above local ground level (representative of ground floor windows) for daytime noise and 4m above ground (representative of 1st floor windows) for night-time noise.

1.2 Construction Noise

1.2.1 CadnaA noise mapping software was used to predict construction noise levels at the selected receptors. The construction noise model followed the procedures for prediction of demolition and construction noise set out in BS 5228-1. Sound power levels for each of the following construction activities have been calculated:

- Scenario 1 – Construction of the BESS and main substation;
- Scenario 2 – Construction of inverters and transformers;
- Scenario 3 – Construction of PV modules; and
- Scenario 4 – Cable installation.

1.2.2 Noise source data for construction plant are presented in Table 11-1. Construction noise predictions were carried out to represent a worst-case scenario where all plant is operational on-site. Consequently, construction noise predictions may overestimate construction noise levels so can be considered as worst case.

Table 11-1 Construction Plant

Work Package	Plant / Equipment	BS 5228 Reference	Sound Power Lw (dBA)	Quantity
Construction of inverters and transformers	Tracked excavator	C.2, Item 14	107	1
	Wheeled loader	C.2, Item 27	108	1
	Wheeled mobile telescopic crane	C.4, Item 38	112	1

Work Package	Plant / Equipment	BS 5228 Reference	Sound Power Lw (dBA)	Quantity
PV Module Construction	Dump truck (tipping fill)	C.2, Item 30	107	2
	Telescopic handler	C.2, Item 35	99	1
	Cement mixer truck (discharging)	C.4, Item 18	103	1
	Articulated dump truck	C.5, Item 16	104	1
	Wheeled mobile telescopic crane	C.4, Item 38	106	1
	Diesel generator	C.4, Item 85	94	1
	Continuous flight auger piling	C.3, Item 17	104	1
	Cement mixer truck (discharging)	C.4, Item 18	103	1
	Dumper	C.4, Item 9	105	1
Construction of BESS and main substation	Tracked excavator	C.2, Item 14	107	2
	Lorry	C.2, Item 34	108	4
	Telescopic handler	C.2, Item 35	99	2
	Continuous flight auger piling	C.3, Item 17	104	1
	Wheeled mobile crane	C.3, Item 30	98	4
	Hand-held welder (welding piles)	C.3, Item 31	101	4
	Generator for welding	C.3, Item 32	101	4
	Gas cutter (cutting top of pile)	C.3, Item 34	96	4
	Mobile telescopic crane	C.4, Item 41	99	2
	Lifting platform	C.4, Item 57	95	4
	Site lift for workers	C.4, Item 62	94	4
	Diesel generator	C.4, Item 85	94	2
	Cable Installation	Tracked excavator	C.4, Item 63	105
Wheeled backhoe loader		C.4, Item 66	97	1
Dumper		C.4, Item 9	105	2
Telescopic handler		C.4, Item 55	98	1
Vibratory roller		C.5, Item 27	95	1
Horizontal Directional Drill	Directional drill (generator)	C.2, Item 44	105	1
	Water pump	C.2, Item 45	93	1
	Tracked excavator	C.2, Item 14	107	1
	Drilling rig	C.3, Item 31	110	1

1.3 Operational Noise

Modelling Methodology

- 1.3.1 Operational noise was modelled in CandnaA, which employs the noise prediction routines commonly used in the UK (e.g. ISO 9613 Acoustics – Attenuation of Sound during Propagation Outdoors – Part 1: Calculation of the absorption of sound by the atmosphere (1993) and Part 2: General Method of Calculation (1996)). The following assumptions and parameters have been used to prepare the noise model:

- Sound source heights for inverters and transformers have been based on information in Chapter 2: The Scheme;
- The central inverter option was modelled, which is considered to be the worst-case option in terms of noise;
- The layout of the BESS and substation assumes that the substation is located in the west of the site and the BESS in the east;
- Three transformers make up the substation;
- 162 units have been assumed for the BESS; and
- Modelling assumes the site is continuously operational during daytime and night-time.

Sound Level Data – Solar Station Inverters and Transformers

- 1.3.2 The proposed inverters are SMA MV power stations which are based on SMA Sunny Central inverters. Manufacturer test data for SMA Sunny Central inverters quotes sound pressure levels of up to 68 dB(A) at a measurement distance of 10 m.
- 1.3.3 Transformers associated with the inverters will have noise emissions approximately 10 dB(A) below that of the inverters. Noise from solar station transformers will not be audible above noise from the inverters and have not been included in the modelling.
- 1.3.4 Inverters have been modelled as vertical area sources with a source height of 3.5 m.

Sound Level Data – BESS Battery Storage Units

- 1.3.5 The proposed battery storage units are based on Gridsol Quantum units with the main noise source being associated cooling fans. The manufacturer has advised each unit has two chillers with a quoted sound pressure levels of 71 dB(A) at a measurement distance of 1.5 m. Battery storage cooling fans have been modelled as area sources with a source height of 2.5 m. Based on experience of similar solar farms, 162 battery storage units were assumed.

Sound Level Data – Substation Transformers

- 1.3.6 Sound level data of substation transformers at the Scheme are based on similar rated transformers for solar plant developments from AECOM library data. An assumed sound power level of 95 dB(A) has been applied for transformers across the Site (including within the BESS and substation areas). Substation transformers have been modelled as vertical and horizontal area sources with a source height of 7 m.